HEARDER MARINE CONSULTANTS P/L A.B.N. 63 002 293 941



4 HARBOUR LANE MIDDLE COVE, NSW 2068 WORK (02) 9417 8208 FAX (02) 9417 3076

West Wanganui

INSURANCE RISK EVALUATION

20428 JOB NO: Without Prejudice TEL: 0407262635 / 0269642585 CLIENT'S NAME: Brian Johns Fax: 0269645854 EMAIL; johnaghri@hotmail.com Box 1550, GRIFFITH NSW 2680 ADDRESS: Aquila D'oro NAME: VESSEL TYPE: Sloop AGX082N REG NO: AU-WWA174392J71 ' HIN: EST AGE/LAUNCHED: 1984 DATE: 1.7.13 Woolwich Dock SIGHTED AT: DRAFT: 8 feet EST SPEED: 9 KNOTS

LENGTH: 54 feet

DESIGNER:

EXTERIOR COLOUR SCHEME: Navy blue topsides. White deck/cabin moulding.

BEAM:

Alan Mummery

arechanging GENERAL DESCRIPTION: Masthead sloop with a fin keel and blade rudder, raked stem, transom stern with a fold out boarding platform long central cabin house and large aft cocknit.

The accommodation consists of a "V" berth cabin forward with a sink unit and storage starboard. To port is an enclosed shower followed by a twin berth cabin with a sink unit with an enclosed head with sink unit starboard. The main cabin has an "L" shaped settee and large "U" shaped galley area port with a settee and navigation station starboard. Aft port and starboard are quarter berths with stail shower aft to port.

BUILDER:

The interior is all clear finished teak with seat and bunk cushions fitted throughout and a laid look ply cabin sole all finished to a high standard.

HULL STRUCTURE:

CONSTRUCTION MATERIAL:

HULL:

Fabricated aluminium

DECK:

Pabricated aluminium

OTHER:

Plywood

CONSTRUCTION TECHNIQUE:

Round bilge plate aluminium

KEEL:

Fabricated aluminium

KEEL BOLTS:

N/A

BALLAST:

All contained in keel

DOCKING STRIP:

N/A

BELTINGS:

N/A

RIBS OR FRAMES:

5 mm thick T section with 5 x 40 mm rider bar

STRINGERS:

Plate on edge.

FLOORS:

8 mm plate with rider plate

BULKHEADS:

Plywood glued in decorative only

FASTENINGS:

S.S bolts and screws

DECK/CABINHOUSE STRUCTURE

HOUSE SIDES:

}

BEAMS:

} All fabricated aluminium

CABIN TOP:

COCKPIT DRAINS:

Through pipes to hul!

DEADLIGHTS AND PORTHOLES:

Fixed deadlights

THROUGH DECK AND COMPANIONWAY OPENINGS: Various aluminium framed deck hatches and main companionway

ENGINES

NO 1 MAKE:

Mitsubishi / Lees

MODEL:

S4E

SERIAL NO:

16130

Hours

3751.01

1 (DE)

TYPE:

4 cylinder

POWER:

Approximately (2) HP

CONTROLS:

Morse cable type

INSTRUMENTS:

Alarms and warning lights, hrs, volts, oil, temp, tacho

AUXILIARY GENERATOR: Alternators on motor only

1 x approx. 60 amps, 1 x 150 amps

MECHANICAL

ENGINE BEDS:

Fabricated aluminium

ENGINE MOUNTS:

Resilient

COUPLING:

Solid

STERN GLAND:

Seal type

STERN BEARINGS:

Appear sound

SKEG:

Aluminium

PROPELLER:

4 Bladed bronze geared feathering - Hunderstead VP2SR system

PROPELLER NUT:

Not examinable

PROPELLER SHAFT: Appears to run true

STEERING GEAR:

Wheel and quadrant type with S/S wire

AUXILIARY STEERING:

N/A

RUDDER STOCK:

Aluminium

RUDDER STOCK GLAND:

Not examinable

RUDDER:

Fabricated aluminium

02/07 2013 TUE 21:26 FAX 61 2 93680552 Marinassess

Z006/009

3

MECHANICAL

ENGINE BEDS:

Fabricated aluminium

ENGINE MOUNTS:

Resilient

COUPLING:

Solid

STERN GLAND:

Seal type

STERN BEARINGS:

Appear sound

SKEG:

Aluminium

PROPELLER:

4 Bladed bronze geared feathering - Hunderstead VP2SR system

PROPELLER NUT:

Not examinable

PROPELLER SHAFT: Appears to run true

STEERING GEAR:

Wheel and quadrant type with S/S wire

AUXILIARY STEERING:

N/A

RUDDER STOCK:

Aluminium

RUDDER STOCK GLAND:

Not examinable

RUDDER:

Fabricated aluminium

SHOWER AND WASHING FACILITIES:

Shower in shower cabin

TOILET SYSTEM:

Electric pump type -direct overboard pump out and holding tank fitted

COOKING FACILITIES:

Force 10,3 burner gas stove and oven

Abode microwave

GAS COMPLIANCE PLATE:

QLD No 570053

REFRIGERATION:

Eutectic fridge/freezer

1 x Waco Coolmatic fridge/freezer

ANCHOR WINCH:

Nilsson electric with deck controls

EQUIPMENT & ACCESSORIES: SAFETY EQUIPMENT

ANCHORS AND WARPS:

1 x CQR & 1 x Danforth with all chain & spare chain and warp

FIRE EXTINGUISHERS:

1 x 3 Kg & 2 x .9Kg - no service tags

FLARES:

4 pack expiry 2015

EPIRB:

GME MT403G expiry October 2015

PFD'S:

8 sighted - not to acceptable standards

OTHER:

RFD 10 man life raft S/n 12317P0014 n expired 2/6/10

Danbuoy

2 x Horseshoe floats

ELECTRONIC AIDS, EQUIPMENT AND ACCESSORIES SIGHTED:

Cockpit

White Star compass Raymarine ST60+ depth Sunteck 180w solar panel

Maincabin

Robertson/Simrad AP20 autopilot

Seiwa Mako plotter

Raythcon Marine Pathfinder 1200

Icom IC-M700UK HF radio

GME GX548 VIIF

Super sound CD/radio

Plastimo clock & barometer

SCA portable solar panel

Tecovision portable TV

Various Deck Corners.

Tender

Achilles LEX88 Hin No: JPACH00027H506

Outboard: Tohatsu 5 HP model M5BS 2005 S/N 012731XE

MAST, SPARS AND RIGGING

MASTS:

wit

Masthead in mast furling aluminium with double in line spreaders - painted

BOOMS:

Aluminium - painted

MAST STEPPING:

Deck stepped

SPIN POLE/JOCKEY POLE:

Aluminium tube type

STANDING RIGGING:

1 x 19 S/S wire

RUNNING RIGGING:

All rope - somewear evident

CHAIN PLATES:

20 mm thick aluminium frames to GRP hull structure

DECK GEAR:

Wilkie winches, blocks and cars &

- Navtec hydraulic backstay adjuster ---

Harkon headsail furler

SAIL INVENTORY, APPROXIMATE AGE AND CONDITION

The sails have been inspected briefly in their bags only to ascertain their condition for valuation.

1 x Main carbon dacron- appears in reasonable condition


1 x furling headsail

1 x staysail

2 x spinnakers

Trysail

Old spare main



OVERALL CONDITION:

For its age this vessel appear to be in very good condition. The navy blue topsides do show some fading and there is some minor marking and scratching but all the varnished timber work and paintwork on the deck is in very good order and internally all the fitout is also in very good order.

For its age the aluminium where it is able to be inspected all appears to be in very good order.

The vessel is very heavily lined internally particularly from the deck down to below the waterline where it has been sprayed with insulating foam and most of this is also covered with plywood and clear plastic panels.


Any further comments in regard to vessel or items as listed:

- a) The starboard navigation light is broken
- b) The compass needs replacement as the lens has gone opaque and the compass cannot be read
- c) The mast and rigging all appear in good condition however we are not aware of the age of the rigging
- d) The vessel is fitted with considerable safety equipment however the fire extinguishers appear to be out of service as well and the life raft, the fire extinguishers should be done on a bi annual basis we highly recommend that prior to another sea passage the life raft be fully serviced and inspected

e)

This survey report expresses the opinion of Hearder Marine Consultants. All reasonable attempts have been made to detect any defects present, however there may exist hidden or latent defects, or those that cannot be discovered without interfering with the vessel's structure. We have not inspected woodwork or other parts of the structure which are covered, unexposed or inaccessible and we are, therefore, unable to report that any such part of the structure is free from defect.

The machinery, electrical and fuel system have been inspected visually only and no guarantee can be given for their satisfactory operation.



2.7.13

A M HEARDER
Shipwright & Naval Architect

DATE